

KANNUR INTERNATIONAL AIRPORT LTD.
PROJECT OFFICE MATTANUR,
KANNUR, KERALA 670 702

KIAL/PROJ.OFFICE/PE/

DATE: 09/04/2013

NOTICE INVITING QUOTATION

Sealed quotations are invited by Managing Director, KIAL, Project Office , Mattanur, Kannur, from contractors of appropriate class of CPWD/MES/P&T/ State PWD/ Railways/PSU's and specialised firms for the work of "**Miscellaneous Civil & Electrical works at KIAL Project Office** ",Mattanur Kannur for an estimated cost of `4,36,000 (Rupees Four Lakh Thirty six Thousand Only). Time allowed is 25 days from the date of award of work.

Quotation forms will be issued up to 17/04/2013 on all working days and recieved till 18/04/2013 up to 1500hrs, and opened on the same day at 1530hrs.

The Scope of works includes:

1. Aluminium partition work
2. Fixing of cooling film on fixed glass in the varandah and rear side room.(cabin 10)
3. Providing and fixing of vertical blinds in the rear side room(cabin10)
4. Providing and fixing of exhaust fan with GI ducting for ventilation
5. Replacing the existing door shutters of conference room and cabin 8 with Aluminium door with prelaminated board and glass with frost film
6. Supplying and fixing Pantry shelf, Notice Board, Tender Box.

Quotation forms along with detailed description, schedule and specifications will be issued to those contractors with relevent experience certificates.

For MANAGING DIRECTOR,
Project Engineer
KIAL, Project Office,
Mattannur, Kannur,
Kerala

**KANNUR INTERNATIONAL AIRPORT
PROJECT OFFICE, MATTANNUR
KANNUR – 670 702**

Ref. No.: KIAL/PROJ-OFFICE/MISCWORKS/NIQ-1/13/

Date:09/04/13

NOTICE INVITING QUOTATIONS

To,

.....
.....
.....
.....
.....

Sub: **NAME OF WORK:** MISCELLANEOUS CIVIL &
ELECTRICAL WORKS AT KIAL PROJECT OFFICE

1. Sealed quotations are invited from contractors for the above work by the Project Engineer in the following address on behalf of the Managing Director, Kannur International Airport Limited.

**PROJECT ENGINEER
KANNUR INTERNATIONAL AIRPORT LTD. (KIAL)
PROJECT OFFICE, MATTANNUR
KANNUR – 670 702**

2. Quotations shall be received by the Project Engineer up to **1500** hours on **18.04.13** and shall be opened at **1530** hours on the same day.
3. The Contractor is advised to study the schedule of quantities. The contractor shall inspect the site deemed to have full knowledge of the work before the quotations are

submitted.

4. The quoted rates shall be firm on F.O.R. Mattannur project/annex office basis and inclusive of all taxes, duties etc, such as excise duty, customs duty, sales tax, octroi, freights, insurance, VAT, service tax etc as applicable. No extra claim shall be entertained in this connection.
5. The quantity shown in schedule may vary during actual execution of work. Increase in quantity of items of work should be made by you at the quoted rates up to a limit of $\pm 25\%$.
6. On completion of work, each item of work shall be jointly measured by you or your authorized representative and the Project Engineer and entered into the measurement book.
 - a. On satisfactory completion of work the final bill shall be submitted by you to the Project Engineer and the same shall be processed.

7. **TERMS OF PAYMENT**

100% payment shall be made to the contractor by KIAL on satisfactory completion of the work, after making statutory deductions and any dues which the contractor may become liable.

8. **COMPLETION PERIOD**

The work shall be completed in all respects within **25 days** which recon from the day of placement of work order.

9. **COMPENSATION FOR DELAY**

Compensation for delay shall be levied @1% per week in case the work is delayed due

to reason beyond the control of KIAL, attributable to the contractor. The amount of compensation thus liveable will be subject to a maximum of 10% work order value.

10. **ENGINEER-IN-CHARGE**

The work shall be approved by the Project Engineer (KIAL), who will be Engineer-in-charge for this work or by his authorized representative.

11. The envelope containing the offer shall superscribe the reference number, name of work and due date/time of opening.

12. KIAL reserves the right to reject any or all quotations and will not be bound to accept the lowest quotation.

Signature
CONTRACTOR

PROJECT ENGINEER
KIAL,MATTANNUR

Name of Work :- MISCELLANEOUS CIVIL & ELECTRICAL WORKS AT KIAL PROJECT OFFICE

SCHEDULE -A

Sl. No:	Description of Item	Unit	Qty	Rate	Amount
1	Supplying and fixing Pure polyester powder coated Aluminium section and prelaminated board & glass with frost film, cutting gypsum board false ceiling and fixing the partition to top of the ceiling for fixity and making good of gypsum board including cost of materials, labour charges etc. complete as per the drawings and specifications .	sqm	60		
2	Supplying and fixing Pure polyester powder coated Aluminium partition with prelaminated board & glass with frost film, door closure and door arrangement including cost of materials, labour charges etc. complete	sqm	13		
3	Supplying and fixing Tender Box (0.45x0.45x0.60m) Aluminium section and prelaminated board including cost of materials, labour charges etc. complete as per specifications .	Each	1		
4	Supplying and fixing Notice Board (1.20 x 0.60 m) made of Aluminium section and prelaminated board having velvet background inside, glass door and lock including cost of materials, labour charges etc. complete as per specifications .	Each	1		
5	Supplying and fixing Pantry Shelf(1.75 x 1.00 x 0.60 m) made of Aluminium section and prelaminated board & plain glass with necessary fittings like lock & key arrangement, handle etc. including cost of materials, labour charges etc. complete as per specifications .	Each	1		
6	Replacing shutters of doors with or without ventilators including removal of shutters, hinges holdfasts and all other fittings and stacking materials with in a distance of 150m.	sqm	5		
7	Providing and fixing Polyster Vertical Blinds of deck' make or equivalent having 100mm width, thickness 0.45 - 0.63mm with acrylic coating having resistance to cracking and fraying as per the approved sample available with KIAL Engineer with suitable powder coated Aluminium Bracket and mechanism for swing arrangement with necessary brackets, screws and turning arrangements, The total arrangement shall be guaranteed for a period of one year for which a separate guarantee shall be executed in a Stamp Paper	sqm	35		
8	Cool Film pasting 50% privacy Garware Brand including all cost, conveyance, labour charges etc. complete	sqm	159		
9	Supplying and fixing Industrial Exhaust Fan of 12" dia, 900RPM Single Phase 1250M3/HR of sound level 30-35 db with support frame work, installing G.I duct of suitable size including cost of materials, labour charges etc. complete as required, make : Almondard or equivalent	Each	1		
10	Supplying and fixing Pure polyester powder coated Aluminium section and prelaminated board with sliding arrangement cost of materials, labour charges etc. complete as per the drawings and specifications .	sqm	1		

Total

(Rupees)

Signature
Contractor

Project Engineer
KIAL